

Resources Regulator

FWP0001717

MT ARTHUR COAL FORWARD PROGRAM

Tuesday 1 July 2025 to Friday 30 June 2028

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Summary

Detail	
Mine	Mt Arthur Coal
Reference	FWP0001717
Forward program commencement date	Tuesday 1 July 2025
Forward program end date	Friday 30 June 2028
Forward program revision (if applicable)	
Contact	James Nixon
Mining leases	CCL 744 (1973), ML 1487 (1992), ML 1593 (1992), ML 1757 (1992), ML 1655 (1992), CL 396 (1973), ML 1739 (1992), ML 1358 (1992), MPL 263 (1973), ML 1548 (1992)
Project location	Hunter Valley Energy Coal Pty Ltd
Date of submission	Tuesday 30 September 2025
Document URL Security reminder: Please exercise caution before opening external links. If a link appears suspicious, avoid clicking it and report it to the Resources Regulator.	https://www.bhp.com/sustainability/environment/regulatory-information

Important

The department may make the information in your program and any supporting information available for inspection by members of the public, including by publication on its website or by displaying the information at any of its offices. If you consider any part of your program to be confidential, please communicate this to the department via the message function on this submission within the Resources Regulator Portal.

Three-year forecast - surface disturbance activities

Project description

HVEC operates MAC comprising an approved open cut (with trucks and shovels to extract up to 32Mtpa of ROM coal) and underground mining operation, a rail loop and associated rail loading facilities located approximately 5 kilometres south west of Muswellbrook in NSW. Coal is crushed and washed, prior to export markets. MAC has modified consent approval to continue operations until 30 June 2030 (MP09_0062-MOD-2). Extraction to date has been occurring at a lesser intensity than the maximum rate authorised by the Project Approval. As a result, the progress of mining as at 2022 shows a different edge of footprint and rehabilitation progression. There are 12 mining and exploration leases and 2 subleases (Maxwell Infrastructure CL395 and CL229).

Description of surface disturbance activities

Exploration activities

This includes definitions and abbreviations. Exploration activities may be undertaken on Mining Act Authorities covered by this plan. These activities may include techniques allowed by these authorities. An exploration drilling program may be undertaken on a campaign basis and subject to operational requirements throughout this period. All exploration boreholes on Mining Leases will be drilled following ecological and cultural heritage (Aboriginal and European) due diligence inspections. Activities on Exploration licences will be undertaken as required by the Licence conditions.

Construction activities

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Resources Regulator

Major activities proposed during this period include: Additional light vehicle roads and tracks. Install upgraded mine infrastructure for noise, dust and water management. Complete installation of tailings infrastructure to support TSF closure and sustain tailings capacity for the mine life including secondary flocculation of the active TSF and installation of tailings pipelines and associated infrastructure to utilise off-lease tailings storage. Ongoing study for Stage 3 – Tailings lifts to raise the wall height of the active TSF. Ongoing construction relating to Hunter River Discharge Improvements. Commence demolition of redundant infrastructure as per the closure management plan.

Mining schedule

Mining development method and sequencing and general mine features.

During this AFP period, mining is proposed to continue within the extended pit shell of Mt Arthur, consisting of: Windmill Pit; Calool Pit; Roxburgh Pit; Ayredale Pit; Mining has occurred at a lesser intensity than the maximum rate of extraction approved by the Project Approval. Prior to excavation of a new open cut strip, pre-stripping operations ensure that natural resources such as vegetation and topsoil are cleared and, where appropriate, recovered for subsequent use in post-mining rehabilitation. Rock strata overlying coal resources (overburden) is drilled and blasted to fracture the rock and facilitate overburden excavation. Hydraulic excavators then excavate and load blasted overburden into large haul trucks. These trucks transport the overburden material to designated emplacement areas. Overburden is placed on the Conveyor Corridor, CD areas, VD areas, Saddlers North and Out Of Pit Dump area. After removing the overburden, the exposed coal seam is mined using hydraulic excavators and loaders. The ROM coal extracted is delivered by haul trucks to either the hopper bins that feed into the CHPP or to the ROM coal stockpiles. After crushing to size and processing to remove impurities, coal is stockpiled prior to transport from site by rail.

Areas identified for emplacements, the sequencing of emplacements, construction, and management.

Overburden emplacement areas that will be utilised include: Visual Dumps 5 (VD5); Contingency Dumps 1 – 5 (CD1-5); Saddlers Dump 1-3 (SD1-3); Belmont Void; Out of Pit Dumps 1N (OP1N) (Previously known as southwest Overburden emplacement area); Tailings

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Resources Regulator

Emplacement Expansion walls; Conveyor Corridor Overburden Emplacement Area; and Ayredale Pit Emplacement areas are generally located within the open cut pit shell on the low wall side of the active pit. However there will be movement to HW dumps. With the exception of the tailings emplacement expansion walls, these emplacement areas are designed by mine planning engineers. The extended tailings emplacement walls were designed by an external consultant. Survey control during emplacement is undertaken by the surveyor teams, under the direction of mine planners. Operational management of the emplacements is undertaken by mine Open Cut Examiners (OCE). Overburden emplacement design incorporates considerations such as capacity, access, shape and lift height, as well as safety and environmental constraints. Emplacement areas are constructed with positive drainage to ensure emplacements shed water away from the active pit. North Pit emplacements (VD1-5 and CD1-5) attain an approximate level of RL 340m to create visual relief. Emplacement design and construction also incorporates structurally weak or contaminated material management considerations.

Processing infrastructure activities and the location of tailings facilities and schedule for emplacement.

Coal handling and processing is undertaken within the centralised CHPP located within Mining Lease ML1487. ROM coal extracted by the approved open cut operations is delivered by truck to either the ROM coal bins or the CHPP ROM coal stockpile. Following processing at the CHPP, coal is loaded onto trains via the rail loading facility for delivery to the export market. Coarse reject material will continue to be co-disposed within overburden emplacement areas or utilised in the construction of stockpile pads, roads or other infrastructure. Fine reject (tailings) will continue to be pumped from the CHPP to the existing approved TSF.

Waste disposal and materials handling operations.

MAC's waste management system has been designed to minimise the generation of waste, maximise reuse and recycling, and meet regulatory requirements. This system consolidates the disposal, tracking and reporting of all waste generated on site. Waste generated as part of MAC's mining activities is sent off site for management. All hydrocarbon handling and storage areas (i.e. diesel storage areas and fill points) are appropriately designed and constructed, incorporating sealed concrete surfaces, bunding and oily water separators, where required. The Contaminated Land Management procedure also outlines the requirements for investigating, reporting, handling, and treating contaminated land. Small volumes of hydrocarbon contaminated material are recovered and disposed of via the regulated

waste management system or remediated at the onsite bioremediation facility.

Key production milestones

MATERIAL	UNIT	YEAR 1	YEAR 2	YEAR 3
Stripped topsoil (if applicable)	(m ³)	90,480	0	0
Rock/overburden	(m ³)	130,600,000	116,400,000	100,700,000
Ore	(Mt)	23	22.8	21.7
Reject material ¹	(Mt)	6.9	6.7	5
Product	(Mt)	16	16.1	16.7

¹This includes coarse rejects, tailings and any other wastes resulting from beneficiation.

Three-year rehabilitation forecast

Rehabilitation planning schedule

Rehabilitation planning schedule

Over the next three years Rehabilitation activities will focus on the Out Of Pit Dump areas, Saddlers and visual dumps, especially around Denman Road area. The estimated schedule for existing rehabilitation maintenance and ongoing improvement works are detailed and tracked in the Mt Arthur Annual Review. Although all these activities are planned to be completed, they are dependent on weather and completion of emplacements to be ready for rehabilitation and therefore should be used as a guide. Actual rehabilitation is provided in the Annual Review. The final landform approved by the Project Approval is necessarily high level and conceptual. HVEC has identified the potential for future changes to final landform, associated with the recent approval (16/4/2025) of the modification of the Project Approval to extend mining operations until 30 June 2030.

Stakeholder consultation

MAC regularly engages with local stakeholders regarding proposed operations, including community engagement programs and opportunities. This engagement includes: The operation of a 24-hour free call community response line to allow the community to contact the operation directly; Access to information including approval documents, environmental assessments, management plans, environmental audits and environmental management and monitoring reports on a publicly accessible website; Regular CCC meetings to provide an interface between the community, mine management and the relevant government departments. The community representatives on the CCC are able to share information from CCC meetings with the wider community and to report back on community issues at CCC meetings; Regular community contact with local Aboriginal stakeholders and stakeholder groups in relation to Aboriginal archaeology and cultural heritage; The MAC Investment Fund which provides financial and in-kind support to local not-for-

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Resources Regulator

profit organisations and partners with community development programs; Regular attendance at monthly meetings of Muswellbrook Chamber of Commerce and Industry Inc, of which Mt Arthur Coal is an active member, to support local business houses and industry; and Participation in the UHMD, coordinated by the NSW Minerals Council to address cumulative impacts from mining in the Upper Hunter and identify opportunities for improved management and innovation.

Rehabilitation studies, risk assessments and/or design work

Acid Mine Drainage Standard - BHP's Global AMD Management Standard is a recently released internal BHP standard that aims to develop a consistent simple, and sustainable global AMD management approach. Species list - MAC continually reviews and updates the applied seed mix listed in the RMP to increase success of rehabilitation. Monitoring Rehabilitation Risk Assessment - Mt Arthur Coal commissioned an independent expert to facilitate an update of the Rehabilitation Risk Assessment as part of this RMP update. Weather Forecasting and Inclusion in Rehabilitation Planning - Undertaking rehabilitation in favourable weather conditions could lead to improved success rate of vegetation establishment and development. Landscape Evolution Model - A review of the legacy rehabilitation areas is proposed by Mt Arthur Coal to determine any risks associated with long-term stability. Should any legacy rehabilitation areas be identified as a risk, they will be included in the development of a Landscape Evolution Model. Topsoil Balance and Growth Medium Trials - A review of the legacy rehabilitation areas is proposed by Mt Arthur Coal to determine any risks associated with long-term stability. Should any legacy rehabilitation areas be identified as a risk, they will be included in the development of a Landscape Evolution Model. Temporary stabilisation - Mulch will be trialed as a temporary erosion control measure while in the ecosystem establishment phase.

Rehabilitation research and trials

RRT NUMBER	PROJECT/TRIAL NAME	OBJECTIVE OF TRIAL/PROJECT	METHODOLOGY	EXPECTED DATE OF COMPLETION	STATUS
RRT0001004	Growth Medium Trials	Develop standard growth media alternatives to topsoil to: Reduce risk of topsoil deficit; Eleminate the weed seed bank risk in topsoil out competing the native species; and Closing the erosion window	Area 1 Following shaping and gypsum application create a friable seed bed and incorporate gypsum Seed directly to shaped spoil Area 2 Following shaping and gypsum application: Padfoot roller or similar to create a friable seed bed and incorporate gypsum Spread hay to depth of ~3cm Seed directly Area 3 Following shaping and gypsum application: Padfoot roller or similar to create a friable seed bed and incorporate gypsum Application of 50m3/ha of rehab grade compost Spread seed directly	1 Jul 2025	Ongoing
RRT0001005	Weather Forecasting and Inclusion in Rehabilitation Planning	Mt Arthur Coal are planning to investigate the use of weather modelling to assist in rehabilitation planning.	TBD	1 Jul 2025	Superseded
RRT0001006	Temporary stabilisation	Trials in the use of surface stabilisation (hay mulch) to reduce short term erosion risks;	Testing various spreading methodologies: - Hay directly to spreader - Hay broken up with excavator pincers then spreader -	1 Jul 2025	Superseded

Resources Regulator

Trialling other equipment

RRT0001104	Erosion modelling	Determine appropriate erosion limits and monitoring processes.	Engage consultant to produce: - Erosion monitoring results based on remote sensing - Predict erosion risk of rehab surfaces to determine hard limits for rehab	1 Jul 2024	Complete
RRT0001105	Temporary Stabilisation	Use of hay mulch for surface stabilisation to reduce short term erosion risks (between seed spreading and cover crop germinating).	Refer FY23 Annual Review	1 Jul 2025	Superseded
RRT0001129	Shallow ripping	Compare shallow ripping of pasture areas to a depth of 200mm compared to 500mm in woodland areas on erosion potential.	An agriplough was utilised in woodland areas where slopes did not extend the operating capacity of the tractor. The steeper woodland areas were dozer ripped. Refer FY24 Annual Review for further details.	1 Jul 2025	Ongoing

Rehabilitation maintenance and corrective actions

Rehabilitation maintenance activities for the next reporting period will include: • Targeted spot weed treatment for woodland areas focusing on: o newly established (FY24 and FY25) rehabilitation in Saddlers North and VD4; o recently revegetated (tubestock and reseeding) areas in MacDonald's South • Tubestock planting planned to occur in VD4 dependent on supply and weather conditions: • Pest animal control programs will be carried out across site. • Pasture maintenance work will be carried out in small areas of North Cut Tailings dam rehab to improve vegetation establishment. • Erosion repair work will be scoped and planned

Rehabilitation schedule

During this three year period, MAC will continue to undertake progressive rehabilitation of the site. Rehabilitation establishment will focus on Saddlers North, OPD, and VD4 and5 emplacement areas. Supplementary planting of targeted rehabilitated areas will occur. General rehabilitation. land management and biodiversity enhancement activities will also continue over previously rehabilitated areas, including but not limited to: Monitoring of biodiversity, pasture development and erosional stability will occur; Ongoing expansion and management of the tailings dam in line with the approved modification for mine closure in 2030; Other activities that will occur over the Forward Program period include: • Responding to regulator comments on ROBJs: • Continued refinement of the draft Completion Criteria: • Continued development of draft woodland performance indicators; • Development of draft performance indicators for pasture areas; • Improvements in the use of analogue sites in assessing rehabilitation performance; • Improvements to pasture monitoring program; • Continued improvement of the GIS rehabilitation tracking system: o Integration GIS monitoring data of TARP triggers; and o Tracking of TARP triggers in the rehabilitation contract.

Completion of rehabilitation

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Resources Regulator

It is Mt Arthur's intent to lodge a partial completion application for rehabilitation completed under the Bayswater Approval - specifically grazing rehabilitation areas completed in the 1990s. Mt Arthur aims to complete consultation with the Resources Regulator prior to this application.

Subsidence remediation for underground operations

Although MAC is located within the Muswellbrook Mine Subsidence district, there is no recent history of mine subsidence within MAC mine leases. As a result, subsidence is not predicted to impact on mining or rehabilitation activities.

Progressive mining and rehabilitation statistics

Three-yearly forecast cumulative disturbance and rehabilitation progression

	Forecast	UNIT	YEAR 1	YEAR 2	YEAR 3
A 1	Total disturbance footprint - surface disturbance	(ha)	6,027.05	6,027.05	6,027.05
0	Total active disturbance	(ha)	4,643.7	4,512.81	4,412.14
Р	Total new area of land proposed for active rehabilitation	(ha)	70.09	200.98	301.65

Rehabilitation key performance indicators (KPIs)

	Forecast	UNIT	YEAR 1	YEAR 2	YEAR 3
0	Total new disturbance area during reporting period	(ha)	86.12		
Р	Total new area of land proposed for rehabilitation during the reporting period	(ha)	70.09	130.89	100.67
Q	Annual rehabilitation to disturbance ratio		0.81	1,015,519.45	

Attachment 1 - Reporting Definitions

REPOR	TING CATEGORY	DEFINITION
Α	Total disturbance footprint - surface disturbance	All areas within a mining lease that either have at some point in time or continue to pose a rehabilitation liability due to surface disturbance activities.
		The total disturbance footprint is the sum of the total active disturbance, decommissioning, landform establishment, growth medium development, ecosystem and land use establishment, ecosystem and land use development and rehabilitation completion (see definitions below). Underground mining operations should not include the footprint of underground mining areas/subsidence management areas in the total disturbance footprint.
В	Total active disturbance	Includes on-lease exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste rock emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped) and temporary stabilised areas (e.g. areas sown with temporary cover crops for dust mitigation and temporary rehabilitation).
С	Rehabilitation - land preparation	Includes the sum of all disturbed land within a mining lease that have commenced

REPORTING CATEGORY		DEFINITION
		any, or all, of the following phases of rehabilitation - decommissioning, landform establishment and growth medium development.
		Refer to the glossary of terms in this document for the definition of these phases of rehabilitation.
D	Ecosystem and land use establishment	Includes the area which has been seeded/planted with the target vegetation species for the intended final land use. However, vegetation has not matured to a stage where it can be demonstrated that it will be sustainable for the long term and or require only a maintenance regime consistent with target reference/analogue sites.
		Typically, rehabilitation areas would be in this phase for at least two years (and usually more) before rehabilitation can be classified as being in the ecosystem and land use development phase. This phase does not apply to infrastructure areas that are being retained as part of final land use for the site.
0		The area of any new active disturbance that will be created during the next three years, as defined under definition A1 (definition A1 Table 5).
Р		The sum of any new rehabilitation to be commenced in the next three years. These areas may be in the phases "Rehabilitation - Land Preparation" or the "Ecosystem & Land Use Establishment" (definitions C & D in Table 5).

FWP0001717 | Tuesday 1 July 2025 to Friday 30 June 2028

Resources Regulator

REPORTING CATEGORY	DEFINITION
Q	The rehabilitation to disturbance ratio (S / R) indicates how many hectares of new rehabilitation are undertaken for each hectare of land disturbed during the three years. A ratio of $1/1$ indicates that the area of new rehabilitation and disturbance in that period are the same.

Attachment 2 - Definitions

WORD	DEFINITION
Active	In the context of rehabilitation, land associated with mining domains is considered 'active' for the period following disturbance until the commencement of rehabilitation.
Active mining phase of rehabilitation	In the context of rehabilitation, the active mining phase of rehabilitation constitutes the rehabilitation activities undertaken during mining operations such as salvaging and managing soil resources, salvaging habitat resources, and native seed collection. This phase also includes management actions taken during operations to manage risks to rehabilitation and enhance rehabilitation outcomes such as selective handling of waste rock and management of tailings emplacements.
Analogue site	In the context of rehabilitation, an analogue site is a 'reference site' that represents an example of the defining characteristics (such as vegetation composition and structure or agricultural productivity) of the final land use. Characteristics of analogue sites can be assessed to develop the rehabilitation objectives and completion criteria for final land use domains.
Annual rehabilitation report and forward program	As described in the Mining Regulation 2016.
Annual reporting period	As defined in the Mining Regulation 2016.

WORD	DEFINITION
Closure	A whole-of-mine-life process, which typically culminates in the relinquishment of the mining lease. It includes decommissioning and rehabilitation to achieve the approved final land use(s).
Decommissioning	The process of removing mining infrastructure and removing contaminants and hazardous materials.
Decommissioning Phase of Rehabilitation	Activities associated with the removal of mining infrastructure and removal and/or remediation of contaminants and hazardous materials. In the context of the rehabilitation management plan this phase of rehabilitation may also include studies and assessments associated with decommissioning and demolition of infrastructure or works carried out to make safe or 'fit for purpose ' built infrastructure to be retained for future use(s) following lease relinquishment.
Department	Department of Primary Industries and Regional Development.
Disturbance	See Surface Disturbance.
Disturbance area	An area that has been disturbed and that requires rehabilitation. This may include areas such as on-licence exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped), and areas requiring rehabilitation that are temporarily stabilised (i.e. managed to minimise dust generation and/or erosion).

WORD	DEFINITION
Domain	An area (or areas) of the land that has been disturbed by mining and has a specific operational use (mining domain) or specific final land use (final land use domain). Land within a domain typically has similar geochemical and/or geophysical characteristics and therefore requires specific rehabilitation activities to achieve the associated final land use.
Ecosystem and Land Use Development	This phase of rehabilitation consists of the activities to manage maturing rehabilitation areas on a trajectory to achieving the approved rehabilitation objectives and completion criteria. For vegetated land uses this phase may include processes to develop characteristics of functional self-sustaining ecosystems, such as nutrient recycling, vegetation flowering and reproduction, and increasing habitat complexity, and development of a productive, self-sustaining soil profile. This phase of rehabilitation may include specific vegetation management strategies and maintenance such as tree thinning, supplementary plantings and weed management.
Ecosystem and Land Use Establishment	This phase of rehabilitation consists of the processes to establish the approved final land use following construction of the final landform. For vegetated land uses this rehabilitation phase includes establishing the desired vegetation community and implementing land management activities such as weed control. This phase of rehabilitation may also include habitat augmentation such as installation of nest boxes.
Exploration	Has the same meaning as that term under the State Environmental Planning Policy (Mining,

WORD	DEFINITION
	Petroleum Production and Extractive Industries) 2007.
Final landform and rehabilitation plan	As defined in the Mining Regulation 2016.
Final land use	As defined in the Mining Regulation 2016.
Form and way	Means the form and way approved by the Secretary. Approved form and way documents are available on the department's website.
Growth Medium Development	This phase of rehabilitation consists of activities required to establish the physical, chemical and biological components of the substrate required to establish the desired vegetation community (including short lived pioneer species.
	This phase may include spreading the prepared landform with topsoil and/or subsoil and/or soil substitutes, applying soil ameliorants to enhance the physical, chemical and biological characteristics of the growth media, and actions to minimise loss of growth media due to erosion.
Habitat	Has the same meaning as that term under the Biodiversity Conservation Act 2016 and the Fisheries Management Act 1994 (as relevant).
Indicator	An attribute of the biophysical environment (e.g. pH, topsoil depth, biomass) that can be used to approximate the progression of a biophysical process. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion

WORD	DEFINITION
	criterion (i.e. defined end point). It may be aligned to an established protocol and used to evaluate changes in a system.
Land	As defined in the Mining Act 1992.
Landform Establishment	This phase of rehabilitation consists of the processes and activities required to construct the final landform.
	In addition to profiling the surface of rehabilitation areas to the approved final landform profile this phase may include works to construct surface water drainage features, encapsulate problematic materials such as tailings, and prepare a substrate with the desired physical and chemical characteristics (e.g. rock raking or ameliorating sodic materials).
Large mine	As defined in the Mining Regulation 2016.
Lease holder	The holder of a mining lease.
Life of mine	The timeframe of how long a mine is approved to mine, from commencement to closure.
Mine rehabilitation portal	Means the Resources Regulator's online portal that lease holders must use (via a registered account) to:

WORD	DEFINITION
	 upload rehabilitation geographical information system (GIS) spatial data develop rehabilitation GIS spatial data (using online tracing functions) generate rehabilitation plans and rehabilitation statistics using the map viewer and Rehabilitation Key Performance Indicator functionalities. Data submitted to the mine rehabilitation portal is collated in a centralised geodatabase for use by
	the Resources Regulator to regulate rehabilitation performance of lease holders.
Mining area	As defined in the Mining Act 1992.
Mining domain	A land management unit with a discrete operational function (e.g. overburden emplacement), and therefore similar geophysical characteristics, that will require specific rehabilitation treatments to achieve the final land use(s).
Mining land	As defined in the Mining Act 1992.
Native vegetation	Has the same meaning as that term under section 60B of the Local Land Services Act 2013.
Overburden	Material overlying coal or a mineral deposit.
Performance indicator	An attribute of the biophysical environment (for example pH, slope, topsoil depth, biomass) that can be used to demonstrate achievement of a rehabilitation objective. It can be measured and audited to

WORD	DEFINITION
	demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion, that is, a defined end point. It may be aligned to an established protocol and used to evaluate changes in a system.
Phases of rehabilitation	The stages and sequences of actions required to rehabilitate disturbed land to achieve the final land use. The phases of rehabilitation are: • active mining • decommissioning • landform Establishment • growth medium development • landform Establishment • ecosystem and land use establishment • ecosystem and land use development
Progressive rehabilitation	The progress of rehabilitation towards achieving the approved rehabilitation completion criteria. This may be described in terms of domains, phases, performance indicators and rehabilitation completion criteria.
Rehabilitation Completion	The final phase of rehabilitation when a rehabilitation area has achieved the approved rehabilitation objectives and rehabilitation completion criteria for the final land use. Rehabilitation areas may be classified as complete when the Resources Regulator has determined in writing that the relevant

WORD	DEFINITION
	rehabilitation obligations have been fulfilled following submission of Form ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate application by the lease holder.
Rehabilitation Completion criteria	As defined in the Mining Regulation 2016.
Rehabilitation cost estimate	As defined in the Mining Regulation 2016.
Rehabilitation management plan	As defined in the Mining Regulation 2016.
Rehabilitation objectives	As defined in the Mining Regulation 2016.
Rehabilitation risk assessment	As defined in the Mining Regulation 2016.
Rehabilitation schedule	The defined timeframes for progressive rehabilitation set out in the forward program.
Relevant stakeholders	Means any persons or bodies who may be affected by the mining operations, including rehabilitation, carried out on the lease land, and includes: • the relevant development consent authority • the local council • the relevant landholder(s) • community consultative committee (if required under the development consent) or equivalent

WORD	DEFINITION
	 consultative group affected land holder(s) government agencies relevant to the final land use affected infrastructure authorities (electricity, telecommunications, water, pipeline, road, rail authorities) local Aboriginal communities, and any other person or body determined by the Minister to be a relevant stakeholder in relation to a mining lease.
Risk	The effect of uncertainty on objectives. It is measured in terms of consequences and likelihood (AS/NZS ISO 31000:2009).
Secretary	The Secretary of the department.
Security deposit	An amount that a mining lease holder is required to provide and maintain under a mining lease condition, to secure funding for the fulfilment of obligations under the lease (including obligations that may arise in the future).
Surface disturbance	Includes activities that disturb the surface of the mining area, including mining operations, ancillary mining activities and exploration.

Resources Regulator

WORD	DEFINITION
Tailings	A combination of the fine-grained solid material remaining after the recoverable metals and minerals have been extracted from the mined ore, and any process water ² .
Waste	Has the same meaning as that term under the Protection of the Environment Operations Act 1997.

²Commonwealth of Australia (DITR), 2007. Tailings Management.

Attachment 3 - Plans

MAC_ForwardPlan_Plan2A_FY26.png

MAC_ForwardPlan_Plan2B_FY27.png

MAC_ForwardPlan_Plan2C_FY28.png

Complete the following lich	ds prior to calculating the Security Deposit.
Mine Name:	Mt Arthur Coal Mine
Lease(s):	ML1358, ML1593, ML1487, ML1548, ML1655, M1757 and ML1739
Title Holder:	Hunter Valley Energy Coal
Term of RCE:	
Current Security:	Date of last Security Deposit review 3/09/20
Mine Contact:	Belinda Bird
List key changes since previous submission:	changes to landform and lowwall/ highwalls due to approval of MOD 2



Open Cut Summary Rehabilitation Cost Estimation

e are automatically filled in from the registration page		
Mt Arthur Coal Mine		
ML1358, ML1593, ML1487, ML1548, ML1655, M1757 and ML1739		
: Hunter Valley Energy Coal		
Date of Leat Sc	ourity Danasit E	2/00/2024
	curity Deposit N	leview: 3/09/2024
Belinda Bird		
Domain		Security Deposit
re		\$42,447,787
•		
		\$82,560,081
		\$86,647,630 \$3,188,564
IL ACTIVITIES		\$3,100,004
nd Sundry Items)		\$214,844,062
	10%	\$21,484,406
nental Monitoring	10%	\$21,484,406
nd Surveying	10%	\$21,484,406
posit for the Mining Project (excl. of GS	T)	\$279,297,281
ed in the above calculation or as part of rehabilitation s	ecurity deposits re	quired by the Department
о то учет то		•
	at the time.	
effection of the total rehabilitation liability held by this mine.		
effection of the total rehabilitation liability held by this mine.		19.09.2025
entative's Name		19.09.2025
	ML1358, ML1593, ML1487, ML1548, ML1655, M13 Hunter Valley Energy Coal Date of Last Se Belinda Bird Domain re Rejects A Waste Reviols Manuary Items Mental Monitoring Ind Surveying Posit for the Mining Project (excl. of GS) and Manuary Items In made to unit prices within this spreadsheet. (Attach a se Illitation design is generally consistent with the development	ML1358, ML1593, ML1487, ML1548, ML1655, M1757 and ML1739 : Hunter Valley Energy Coal Date of Last Security Deposit R Belinda Bird Pomain re Rejects a & Waste a & Voids nt Activities nd Sundry Items) nental Monitoring 10% hental Monitoring 10%

Complete the following field	ds prior to calculating the Security Deposit.
Mine Name:	Mt Arthur Coal Mine
Lease(s):	CL744, CL396, MPL263
Title Holder:	Mt Arthur Coal
Term of RCE:	
Current Security:	Date of last Security Deposit review 3/0
Mine Contact:	Belinda Bird
List key changes since previous submission:	Changes to landform and lowwall/ highwalls due to approval of MOD 2



Open Cut Summary Rehabilitation Cost Estimation

e are automatically filled in from the registration page		
Mt Arthur Coal Mine		
CL744, CL396, MPL263		
Mt Arthur Coal		
Date of Last S	ecurity Denosit Review	3/09/2024
	Topolitical	3.33.232
Bollida Bild		
Domain	Se	curity Deposit
		\$18,916,218
		\$69,102,815
-		\$11,389,932
		\$8,225,319
		\$3,023,283
d Sundry Items)		\$110,657,567
a current terms,		\$110,037,307
ental Monitoring	10%	\$11,065,757
nd Surveying	3%	\$3,319,727
oosit for the Mining Project (excl. of GST	r)	\$125,043,051
d in the above calculation or as part of rehabilitation se	ocurity donocite required by	v the Department
•		•
made to unit prices within this spreadsheet. (Attach a sep	parate sheet providing details	•
•	parate sheet providing details	•
made to unit prices within this spreadsheet. (Attach a sep	parate sheet providing details consent for the project.	•
made to unit prices within this spreadsheet. (Attach a septration design is generally consistent with the development ion has been estimated using the best available information	parate sheet providing details consent for the project.	•
	CL744, CL396, MPL263 Mt Arthur Coal Date of Last S Belinda Bird Domain e ejects & Waste & Voids t Activities d Sundry Items) ental Monitoring nd Surveying Dosit for the Mining Project (excl. of GST	Mt Arthur Coal Mine CL744, CL396, MPL263 Mt Arthur Coal Date of Last Security Deposit Review. Belinda Bird Pomain See ejects & Waste & Voids t Activities d Sundry Items) ental Monitoring d Surveying 10% and Surveying 3% posit for the Mining Project (excl. of GST)